Designer Contracts									
	Method Statement								
Preliminary Information									
Method statement title	Fitting Solid Wood Flooring								
Description of works	General Fitting Solid Wood Flooring								
Resources Personal details ( including est	imated employee numbers/trades and working hours)								
Designer Contracts Staff Sub-Contractor Fitters									
H&S Training, CITB SSP & HS	g - All staff who visit site All staff								
Sub-Contractor work Element Fitting Solid Wood Flooring.	/ Personnel (including type of sub-contracted work and workforce size/trades)								
arrangements for young pe	regular basis and work closely with Site Management and attend all meetings								

#### Plant / Equipment requirement details (including vehicle movement and inspection/maintenances/testing arrangements)

plant used on site.

Dust Suppression for chopsaw/joiner to be Class M.

Handsaw, jigsaw, chopsaw, workbench, block & hammer, architrave cutter pin gun, portable drill, plane knives, hoover, biscuit joiner.

Ensure that all portable appliances are portable appliance tested and have the relevant certificate.

# Materials, Movement and storage details (including control of manual handling, movement between levels, traffic interface and ignition)

Solid Wood, doorbars, screws, raw plugs.

Materials will be brought to site by sub contractors with on site movements controlled by site contractors All materials to be delivered to work area and unloaded. All materials will be stacked in accordance with health & safety working practices.

All adhesives to be handled with care.

Adhesives only to be used in well ventilated areas.

Adhesives only to be used in well ventilated areas.

### Sequence of work ( including site access, preparation and co-ordination of work)

Fitter examines the area to be fitted and ensures that it is clear of obstacles.

Materials are taken into plot and stored in a suitable area to acclimatise.

Scrape and hoover clean the floor before any floor preparation takes place.

Bottom of doors are cut using handsaw, lay underlay in relevant areas.

Lay and fit solid wood into positions using a block & hammer.

Wood cut to size using jigsaw & workbench outside if possible or well ventilated area using dust extraction.

Attach beading to skirting board using pin gun.

Cut door bars to size using a jigsaw and plane where necessary and screw into position.

Remove all waste from site and return to Designer Contracts warehouse for safe disposal.

Remove all tools from site and hoover floor clean. Check the floor before leaving.

## Risk Assessment(s) for Significant Risks

Are there risk assessments for:	Yes	No	N/A	Risk Assessment Titles
Access / egress	Х			Site Specific Risk Assessment
Place of Work	Х			Site Specific Risk Assessment
Others at risk (eg public)			х	Site Specific Risk Assessment
				Relevant COSHH assessments depending on product used
COSHH, noise, vibration, fire etc	Х			- Head Office will provide this
Environmental risks (inc asbestos/silica dust)		х		Site Specific Risk Assessment
Sub-contracted activities	Х			Site Specific Risk Assessment
Control Measures to be used				

	Yes	No	N/a	Control Measure Name
Permit required			х	
Security Arrangements			х	
Special training (confined space, tower erection,				
use of plant, spills control etc)			Х	

Personal Protective Equipment Requirements							
	Yes	No	N/a	Control Measure Name			
				Hard Hats must be worn by everyone			
Safety Headgear	Х			when onsite.			
Safety Footwear	х			Safety footwear is required at all times			
· · ·				High visibility vest/jacket must be			
High visibility clothing	Х			worn at all times.			
				cut level 5 for use with knives &			
Safety Gloves	Х			chisels			
Hearing protection	х			when using chopsaw			
Eye protection	х			when using powertools			
				This activity is below the workplace			
Respiratory Protection			x	exposure limit set by HSE set by the HSE			
Leg/Knee protection	Х			Wear knee pads when kneeling			
Arm/elbow protection			x				
Fall arrest equipment			x				
Overalls / aprons			х				
Other PPE			х				

Emergency Arrangements								
	Yes	No	N/A					
Rescue	Х							

Details of rescue arrangements
--------------------------------

The company will fully comply with all emergency procedures developed by the site. Any changes in the emergency procedures and exit routes shall be provided by the site to our Regional Manager in order that such changes can be communicated to the workforce.

		Yes	No	N/A
Special first aid requirements		Х		

# Details of special first aid arrangements Follow site rules for all first aid requirements and fitters to use site first aid facilities. Follow first aid instructions given on relevant COSHH risk assessments

		Yes	No	N/A
Spillage Containment		Х		

### Details of spillage containment

Follow spillage containment instructions given on relevant COSHH assessment.

### **Temporary Amended Systems**

	Yes	No	N/a	Comments
Traffic routes	х			Follow all site signs
				Report any accidents, emergencies or incidents to site office & Designer Contracts Line Manager. Always carry a fully charged
Emergency arrangements	Х			mobile phone
Services			х	
Other			Х	

### **Monitoring and Compliance**

	Yes	No	N/a	Comments
Monitoring arrangements			Х	Ongoing monitoring by RM/SCM
Enforcement arrangements			х	

### **General Comments**

We monitor health & safety by using a computerised health & safety management system called

BusinessSafe Online which is provided by Peninsula Business Services Limited

The Regional Manager/Senior Contracts Manager visit sites on a regular basis to monitor all aspects of work and health & safety. The health & safety department ensures that all hazards of specific work activities, risk & COSHH assessments are recorded onto BusinessSafe Online which we also use for accident reporting and to indicate what training staff have undertaken and when this needs updating. The health & safety Director is responsible for reviewing reports which have been compiled as a result of monitoring health & safety and the Regional Manager/Senior Contracts Manager are then responsible for ensuring any corrective actions necessary are carried out.