Designer Contracts						
	Method Statement					
Preliminary Information						
Method statement title	Fitting Laminate					
Description of works	General Fitting Laminate					
Resources						
	stimated employee numbers/trades and working hours)					
Designer Contracts Staff Sub-Contractor Fitters						
H&S Training, CITB SSP & H	ng - All staff who visit site All staff					
Sub-Contractor work Element Fitting laminate.	t / Personnel (including type of sub-contracted work and workforce size/trades)					
arrangements for young pe	a regular basis and work closely with Site Management and attend all meetings					

Plant / Equipment requirement details (including vehicle movement and inspection/maintenances/testing arrangements)

No plant used on site.

Handsaw, jigsaw, chopsaw, workbench, block & hammer, architrave cutter pin gun, portable drill, plane knives, broom.

Ensure that all portable appliances are portable appliance tested and have the relevant certificate.

Materials, Movement and storage details (including control of manual handling, movement between levels, traffic interface and ignition)

Laminate, doorbars, screws, raw plugs.

Materials will be brought to site by sub contractors with on site movements controlled by site contractors All materials to be delivered to work area and unloaded. All materials will be stacked in accordance with

health & safety working practices.

All adhesives to be handled with care.

Adhesives only to be used in well ventilated areas.

Sequence of work (including site access, preparation and co-ordination of work)

Fitter examines the area to be fitted and ensures that it is clear of obstacles.

Materials are taken into plot and stored in a suitable area to acclimatise.

Scrape and sweep clean the floor before any floor preparation takes place.

Bottom of doors are cut using handsaw, lay underlay in relevant areas.

Lay and fit laminate into positions using a block & hammer.

Laminate is cut to size using jigsaw & workbench outside if possible or well ventilated area. If not possible

fitters are required to wear FFP3 face masks. Attach beading to skirting board using pin gun.

Cut door bars to size using a jigsaw and plane where necessary and screw into position.

Remove all waste from site and return to Designer Contracts warehouse for safe disposal.

Remove all tools from site and sweep floor clean. Check the floor before leaving.

Risk Assessment(s) for Significant Risks

Are there risk assessments for:	Yes	No	N/A	Risk Assessment Titles
Access / egress	х			Site Specific Risk Assessment
Place of Work	х			Site Specific Risk Assessment
Others at risk (eg public)			x	Site Specific Risk Assessment
COSHH, noise, vibration,fire etc	х			Relevant COSHH assessments depending on product used - Head Office will provide this
Environmental risks (inc asbestos/silica dust)		x		Site Specific Risk Assessment
Sub-contracted activities	х			Site Specific Risk Assessment
Control Measures to be used				

	Yes	No	N/a	Control Measure Name
Permit required			х	
Security Arrangements			х	
Special training (confined space, tower erection,				
use of plant, spills control etc)			х	

Personal Protective Equipment Requirements				
	Yes	No	N/a	Control Measure Name
				Hard Hats must be worn by
Safety Headgear	Х			everyone when onsite.
_				Safety footwear is required at all
Safety Footwear	Х			times
				High visibility vest/jacket must be
High visibility clothing	X			worn at all times.
Safety Gloves	x			Gloves for cutting/spraying adhesive
Hearing protection			Х	
Eye protection	x			Required when cutting laminate
		1		Fitters are required to wear FFP3
Respiratory Protection	Х			face masks.
Leg/Knee protection	x			Wear knee pads when kneeling
Arm/elbow protection			x	
Fall arrest equipment			x	
Overalls / aprons			x	
Other PPE			Х	

Emergency Arrangements								
				Yes	No	N/A		
Rescue				х				

The company will fully comply with all emerged	ncy procedures dev	veloped b	y the site.								
Any changes in the emergency procedures and	l exit routes shall be	e provide	d by the site								
to our Regional Manager in order that such cha	anges can be comm	nunicated	to the work	force.							
				Yes	No	N/A					
				Yes	No	N/A					

Details of special first aid arrangements	
ollow site rules for all first aid requirements and fitters to use site first aid facilities.	
ollow first aid instructions given on relevant COSHH risk assessments	

				Yes	No	N/A		
Spillage Containment				х				
Details of spillage containment								
Follow spillage containment instructions given on re	elevant COS	HH assessm	nent.					

Temporary Amended Systems

	Yes	No	N/a	Comments
Traffic routes	х			Follow all site signs
Emergency arrangements	x			Report any accidents, emergencies or incidents to site office & Designer Contracts Line Manager. Always carry a fully charged mobile phone
Services			Х	
Other			х	

Monitoring and Compliance

	Yes	No	N/a	Comments
Monitoring arrangements			х	Ongoing monitoring by RM/SCM
Enforcement arrangements			Х	

General Comments

We monitor health & safety by using a computerised health & safety management system called BusinessSafe Online which is provided by Peninsula Business Services Limited

The Regional Manager/Senior Contracts Manager visit sites on a regular basis to monitor all aspects of work and health & safety. The health & safety department ensures that all hazards of specific work activities, risk & COSHH assessments are recorded onto BusinessSafe Online which we also use for accident reporting and to indicate what training staff have undertaken and when this needs updating. The health & safety Director is responsible for reviewing reports which have been compiled as a result of monitoring health & safety and the Regional Manager/Senior Contracts Manager are then responsible for ensuring any corrective actions necessary are carried out.