Designer Contracts

Method Statement

Preliminary Information Method statement title	Fitting Matting
method statement title	Treeting Wildering
Description of works	General Fitting Matting

Description of works	General Fitting Matting
Resources	
Personal details (including est	imated employee numbers/trades and working hours)
Designer Contracts Staff	
Sub-Contractor Fitters	
	training, competency and experience requirements for both operatives & supervisors)
•	E - All Managers who visit sites carry CSCS Card
H&S Training - All Fitters wh	o visit site will carry CSCS card
SSSTS - All Senior Contracts	Managers
Asbestos Awareness Trainin	g - All staff who visit site
Manual Handling Training - A	All staff
Site Induction Training & To	olbox Talks - All Fitters

Sub-Contractor work Element / Personnel (including type of sub-contracted work and workforce size/trades)

Handling and laying of matting.

Supervisor details and arrangements (including supervisor/operatives ratio, sub-contractor supervision details and arrangements for young persons/apprentices)

Managers to supervise on a regular basis and work closely with Site Management and attend all meetings as required to relay information to there teams.

Plant / Equipment requirement details (including vehicle movement and inspection/maintenances/testing arrangements) No plant used on site. Materials, Movement and storage details (including control of manual handling, movement between levels, traffic interface and

Materials, Movement and storage details (including control of manual handling, movement between levels, traffic interface and ignition)

Matting.

Materials will be brought to site by sub contractors with on site movements controlled by site contractors All materials to be delivered to work area and unloaded. All materials will be stacked in accordance with health & safety working practices.

All adhesives to be handled with care.

Adhesives only to be used in well ventilated areas.

Sequence of work (including site access, preparation and co-ordination of work)

Check condition of ground surface i.e wet ground.

Check ground surface for obstructions before loading/unloading van.

Ensure floors are swept and in good condition before rolling out underlay.

Fit and cut matting to net area for room/staircase

Staple underlay to wood floors ensuring staples are straight and not proud

Spray adhesive underlay to concrete floors to avoid movement

Remove all waste from site and return to Designer Contracts warehouse for safe disposal. Remove all tools from site and sweep floor clean. Check the floor before leaving.

Risk Assessment(s) for Significant Risks

Are there risk assessments				
for:	Yes	No	N/A	Risk Assessment Titles
Access / egress	Х			Site Specific Risk Assessment
Place of Work	Х			Site Specific Risk Assessment
Others at risk (eg public)			х	Site Specific Risk Assessment
COSHH, noise, vibration, fire etc	Х			Relevant COSHH assessments depending on product used - Head Office will provide this
Environmental risks (inc asbestos/silica dust)		Х		Site Specific Risk Assessment
Sub-contracted activities	Х			Site Specific Risk Assessment

Control Measures to be used

	Yes	No	N/a	Control Measure Name
Permit required			Х	
Security Arrangements			Х	
Special training (confined space, tower erection,				
use of plant, spills control etc)			Х	

Personal Protective Equipment Requirements

	Yes	No	N/a	Control Measure Name
				Hard Hats must be worn by
Safety Headgear	X			everyone when onsite.
				Safety footwear is required at all
Safety Footwear	Х			times
High visibility clothing	Х			High visibility vest/jacket must be worn at all times.
Safety Gloves	Х			Gloves for cutting/spraying adhesive
Hearing protection			Х	
Eye protection			Х	
Respiratory Protection			x	This activity is below the workplace exposure limit
Leg/Knee protection	Х			Wear knee pads when kneeling
Arm/elbow protection			Х	
Fall arrest equipment			Х	
Overalls / aprons			Х	
Other PPE			Х	

Emergency Arrangements

		Yes	No	N/A
Rescue		Х		

Details of rescue arrangements

The company will fully comply with all emergency procedures developed by the site.

Any changes in the emergency procedures and exit routes shall be provided by the site to our Regional Manager in order that such changes can be communicated to the workforce.

		Yes	No	N/A
Special first aid requirements		Χ		

Details of special first aid arrangements

Follow site rules for all first aid requirements and fitters to use site first aid facilities.

Follow first aid instructions given on relevant COSHH risk assessments

		Yes	No	N/A
Snillage Containment		>		
Spillage Containment		Χ		

Details of spillage containment

Follow spillage containment instructions given on relevant COSHH assessment.

Temporary Amended Systems

	Yes	No	N/a	Comments
Traffic routes	Х			Follow all site signs
Emergency arrangements	X			Report any accidents, emergencies or incidents to site office & Designer Contracts Line Manager. Always carry a fully charged mobile phone
Services			х	
Other			Х	

Monitoring and Compliance

	Yes	No	N/a	Comments
Monitoring arrangements			Х	Ongoing monitoring by RM/SCM
Enforcement arrangements			Х	

General Comments

We monitor health & safety by using a computerised health & safety management system called BusinessSafe Online which is provided by Peninsula Business Services Limited

The Regional Manager/Senior Contracts Manager visit sites on a regular basis to monitor all aspects of work and health & safety. The health & safety department ensures that all hazards of specific work activities, risk & COSHH assessments are recorded onto BusinessSafe Online which we also use for accident reporting and to indicate what training staff have undertaken and when this needs updating. The health & safety Director is responsible for reviewing reports which have been compiled as a result of monitoring health & safety and the Regional Manager/Senior Contracts Manager are then responsible for ensuring any corrective actions necessary are carried out.